LUCK EDGEFIELD - CONCEPTUAL PLAN LUCK STONE CORPORATION

EDGEFIELD COUNTY, SOUTH CAROLINA

FEBRUARY 15, 2024

SITE DATA

PARCEL ID(S): 058-00-00-039-00

SITE ADDRESS: RD 659D

CLARKS HILL, SOUTH CAROLINA 29821

SITE ACREAGE: 424.8 ACRES
EXISITING ZONING: UN-ZONED

PROPOSED USE: AGGREGATE MINE OPERATIONS

LATITUDE: 33°37'36.0"N (33.6267°)
LONGITUDE: 82°04'34.9"W (-82.0764°)

RIVER BASIN: SAVANNAH
RECEIVING WATERBODY: STEVENS CREEK

OWNER: LUCK STONE CORPORATION

ADDRESS: 515 STONE MILL DRIVE (PO BOX 29682)

RICHMOND, VIRGINIA 23242

PHONE NO.: (804) 784-6300
CONTACT NAME: BRUCE SMITH

CONTACT E-MAIL ADDRESS: BRUCESMITH@LUCKCOMPANIES.COM

PROJECT REPRESENTATIVE: S&ME INC.

CONTACT E-MAIL ADDRESS:


ADDRESS: 2016 ARSLEY TOWN BLVD. SUITE 2-A

CHARLOTTE, NC 28273

CRUHL@SMEINC.COM

PHONE NO.: (704) 523-4726

CONTACT NAME: CEDRIC H. RUHL, P.E.



PREPARED FOR



515 STONE MILL DRIVE RICHMOND, VIRGINIA 23242 (804)784-6300 PREPARED BY



2016 AYRSLEY TOWN BLVD. SUITE 2-A CHARLOTTE, NC 28273 (704) 523-4726

IIILE

NUMBER TITLE

) COVER

1 EXISTING CONDITIONS PLAN

DRAWINGS

2 SITE LAYOUT

DETAILS (1 OF 6)

DETAILS (2 OF 6)

DETAILS (3 OF 6)


DETAILS (4 OF 6)


7 DETAILS (5 OF 6)


8 DETAILS (6 OF 6)



THESE DRAWINGS HAVE BEEN PREPARED BY S&ME FOR OUR CLIENT'S USE. WRITTEN APPROVAL FROM S&ME SHALL BE OBTAINED PRIOR TO ANY THIRD-PARTY USE, MODIFICATION, AND REPRODUCTION, OR RELIANCE, EXCEPT AS REQUIRED BY LAW. S&ME ACCEPTS NO RESPONSIBILITY, AND DENIES ANY LIABILITY WHATSOEVER, TO ANY PARTY THAT USES OR RELIES ON THESE DRAWINGS WITHOUT S&ME'S EXPRESS WRITTEN CONSENT.







14-FT.

10-FT.

HDPE LINER

PLAN VIEW

13-FT.

SECTION VIEW

─ 30 MIL.

HDPE LINER

17-FT.

1-FT.—

GENERAL NOTES

- 1. DUE TO SITE CONSTRAINTS THE WIDTH AND LENGTH MAY BE ADJUSTED BASED ON CONDITIONS IN THE FIELD.
- 2. APPROPRIATE SIGNAGE WILL BE POSTED ALONG THE ROAD TO INFORM THE GENERAL
- PUBLIC OF POTENTIAL CONSTRUCTION TRAFFIC PER REQUIREMENTS. 3. STOCKPILE TOPSOIL FROM CONSTRUCTION ENTRANCE INSTALLATION. USE TOPSOIL FOR
- BACKFILL AFTER REMOVAL OF CONSTRUCTION ENTRANCE DURING FINAL CLEANUP. 4. THE NEAREST UPSTREAM AND DOWNSTREAM CULVERT DIAMETER(S) WILL BE OBSERVED AT EACH LOCATION A CONSTRUCTION ENTRANCE IS TO BE INSTALLED WITHIN A ROADSIDE SWALE/DITCH. DIAMETER OF TEMPORARY CULVERT SHALL BE THE LARGER OF EITHER THE CULVERT, BUT NO LESS THAN 18-IN. IN DIAMETER. CONTRACTOR SHALL FIELD
- INSTALL 18-IN. DIA. COMPOST FILTER SOCK CHECK DAMS IN ROADSIDE SWALE/DITCH AT
- UPSTREAM AND DOWNSTREAM LOCATIONS OF LIMITS OF DISTURBANCE. 6. THE CONSTRUCTION ENTRANCE AND CULVERT (IF PRESENT), WILL BE REMOVED WHEN
- SEDIMENT FROM THE ENTRANCE WILL BE HAULED OFF-SITE AND DISPOSED OF PROPERLY 7. UPON REMOVAL OF THE CONSTRUCTION ENTRANCE, THE CONTRACTOR SHALL BRING THE AREA TO ORIGINAL GRADE AND STABILIZE IT. IF A TEMPORARY CULVERT WAS UTILIZED IN CONJUNCTION WITH THE CONSTRUCTION ENTRANCE, THE CONTRACTOR SHALL INSTALL EROSION CONTROL BLANKET AND 18-IN. DIA. COMPOST FILTER SOCK
- CHECK DAMS WITHIN ROADSIDE SWALE/DITCH. 8. EROSION CONTROL BLANKET SHALL BE NORTH AMERICAN GREEN BIONET SC150BN OR
- ENGINEER APPROVED EQUIVALENT.
- 9. INSTALL THREE 18-IN. DIA. COMPOST FILTER SOCK CHECK DAMS IN EACH IMPACTED SWALE/DITCH; UPSTREAM, DOWNSTREAM, AND MIDDLE OF OF SWALE/DITCH.

MAINTENANCE NOTES

- 1. ALL SEDIMENT AND EROSION CONTROLS SHALL BE INSPECTED AT LEAST ONCE EVERY SEVEN CALENDAR DAYS AND AFTER ANY STORM EVENT OF GREATER THAN 0.5 INCHES OF PRECIPITATION DURING ANY 24-HOUR PERIOD. INSPECTIONS MUST BE CONDUCTED UNTIL FINAL STABILIZATION IS REACHED ON ALL AREAS OF THE CONSTRUCTION SITE.
- 2. THE ENTRANCE WILL BE MAINTAINED IN A CONDITION THAT WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO EXISTING ROADWAYS. SEDIMENT TRACKED, SPILLED, DROPPED OR OTHERWISE DEPOSITED ONTO ROADWAYS WILL BE SWEPT UP AS SOON AS PRACTICAL AND PLACED BACK WITHIN THE APPROVED DISTURBED AREA.
- 3. IF EXCESS SEDIMENT HAS CLOGGED THE STONE, THE ENTRANCE WILL BE TOPDRESSED WITH NEW STONE AS NEEDED. REPLACEMENT OF THE STONE MAY BECOME NECESSARY WHEN THE STONE BECOMES ENTIRELY FILLED WITH SEDIMENT AND MUD.

REFERENCE: DETAIL BASED ON SCDHEC STORM WATER MANAGEMENT BMP HANDBOOK DATED JULY 31, 2005 (PORTIONS REVISED MAY 2014).

CONSTRUCTION ENTRANCE SCALE: N.T.S.


GENERAL NOTES

- 1. ACTUAL LOCATION DETERMINED IN FIELD.
- 2. CONCRETE WASHOUT STRUCTURES REQUIRING ADDITIONAL CAPACITY SHALL INCLUDE EXCAVATED PIT BENEATH HDPE LINER OF WASHOUT RETENTION AREA. DEPTH OF PIT VARIES DEPENDING ON REQUIRED CAPACITY.
- 3. CONCRETE WASHOUT STRUCTURE NEEDS TO BE CLEARLY MARKED WITH SIGNAGE NOTING DEVICE WITH LETTERS A MINIMUM
- OF 5-IN. IN HEIGHT AND WITHIN 30-FT. OF STRUCTURE.
- 4. DO NOT DISCHARGE CONCRETE OR CEMENT SLURRY FROM THE SITE.
- 5. INSTALL TEMPORARY CONCRETE WASHOUTS PER LOCAL REQUIREMENTS, WHERE APPLICABLE. IF AN ALTERNATE METHOD OR PRODUCT IS TO BE USED, CONTACT YOUR APPROVAL AUTHORITY FOR REVIEW AND APPROVAL. IF LOCAL STANDARD DETAILS ARE NOT AVAILABLE, USE THIS DETAIL. IF THIS DETAIL IS USED, OWNER'S DESIGNATED ENVIRONMENTAL REPRESENTATIVE MAY APPROVE ALTERNATIVE MATERIALS PRIOR TO INSTALLATION.
- 6. DO NOT USE CONCRETE WASHOUTS FOR DEWATERING OR STORING DEFECTIVE CURB OR SIDEWALK SECTIONS. STORMWATER ACCUMULATED WITHIN THE WASHOUT MAY NOT BE PUMPED INTO OR DISCHARGED TO THE STORM DRAIN SYSTEM OR RECEIVING SURFACE WATERS. LIQUID WASTE MUST BE PUMPED OUT AND REMOVED FROM PROJECT.
- 7. LOCATE WASHOUTS AT LEAST 50-FT. FROM STORM DRAIN INLETS AND SURFACE WATERS UNLESS IT CAN BE SHOWN THAT NO OTHER ALTERNATIVES ARE REASONABLY AVAILABLE. AT A MINIMUM, INSTALL PROTECTION OF STORM DRAIN INLET(S) CLOSEST TO THE WASHOUT WHICH COULD RECEIVE SPILLS OR OVERFLOW.
- 8. LOCATE WASHOUTS IN AN EASILY ACCESSIBLE AREA, ON LEVEL GROUND AND INSTALL A STONE ENTRANCE PAD IN FRONT OF
- THE WASHOUT. ADDITIONAL CONTROLS MAY BE REQUIRED BY THE APPROVING AUTHORITY. 9. INSTALL AT LEAST ONE SIGN DIRECTING CONCRETE TRUCKS TO THE WASHOUT WITHIN THE PROJECT LIMITS. POST SIGNAGE ON THE WASHOUT ITSELF TO IDENTIFY THIS LOCATION.

MAINTENANCE NOTES

- 1. THE CONCRETE WASHOUT STRUCTURES SHALL BE MAINTAINED WHEN THE LIQUID AND/OR SOLID REACHES 1/2 OF THE
- STRUCTURES CAPACITY TO PROVIDE ADEQUATE HOLDING CAPACITY WITH A MINIMUM 6-IN. OF FREEBOARD. 2. DISPOSE OF, OR RECYCLE SETTLED, HARDENED CONCRETE RESIDUE IN ACCORDANCE WITH LOCAL AND STATE SOLID WASTE
- REGULATIONS AND AT AN APPROVED FACILITY. 3. MANAGE WASHOUT FROM MORTAR MIXERS IN ACCORDANCE WITH THE ABOVE ITEM AND IN ADDITION PLACE THE MIXER AND
- ASSOCIATED MATERIALS ON IMPERVIOUS BARRIER AND WITHIN LOT PERIMETER SILT FENCE.
- 4. REMOVE LEAVINGS FROM THE WASHOUT WHEN AT APPROXIMATELY 1/2 CAPACITY TO LIMIT OVERFLOW EVENTS. REPLACE THE HDPE LINER, SAND BAGS OR OTHER TEMPORARY STRUCTURAL COMPONENTS WHEN NO LONGER FUNCTIONAL. WHEN UTILIZING ALTERNATIVE OR PROPRIETARY PRODUCTS, FOLLOW MANUFACTURER'S INSTRUCTIONS.
- 5. AT THE COMPLETION OF THE CONCRETE WORK, REMOVE REMAINING LEAVINGS AND DISPOSE IN AN APPROVED DISPOSAL FACILITY. STABILIZE ANY DISTURBANCE CAUSED BY REMOVAL OF WASHOUT.

REFERENCE: DETAIL BASED ON SCDHEC STORM WATER MANAGEMENT BMP HANDBOOK DATED JULY 31, 2005, REVISED MARCH 2014, AND NCDEQ EROSION AND SEDIMENT CONTROL PLANNING AND DESIGN MANUAL, CHAPTERS 6 AND 8 REVISED, MAY





— 18-IN. DIA. COMPOST

- 18-IN. DIA. COMPOST

FILTER SOCK


FILTER SOCK

CHANNEL NOTES:

- SEE PLAN SHEETS FOR CHANNEL LOCATION. DIMENSIONING AND STABILIZATION MATTING (TYPE SPECIFIED IN TABLE OR ENGINEER
- APPROVED EQUIVALENT) 3. SEE DRAWINGS FOR CHECK DAM/SEDIMENT TUBE LOCATION AND SPACING WITHIN CHANNELS.

CHANNEL SUMMARY TABLE										
CHANNEL ID	AVERAGE LONGITUDINAL SLOPE (FT./FT.)	BOTTOM WIDTH (FT.)	LEFT SIDE SLOPE (XH:1V)	RIGHT SIDE SLOPE (XH:1V)	CHANNEL DEPTH (FT.)	CHANNEL MATTING				
THE CHANNEL CHANA DV TARIE WILL BE RORLILATED FOLLOWING THE DETAILED DECICAL										

THE CHANNEL SUMMARY TABLE WILL BE POPULATED FOLLOWING THE DETAILED DESIGN.



START ANCHOR TRENCH

(NOTE 3)

2-FT.

φ, ο'ο ο φ

0 0 0 0

MEDIUM FLOW CHANNEL

3.4 STAPLES PER SQ.YD.

4-FT. Φ| Ο_ΤΟ Ο

ROLL DIRECTION —

EDGE ANCHOR TRENCH

4-IN. TO

6-IN.

(NOTE 4)

END ANCHOR TRENCH

(NOTE 2)



4-IN.

(NOTE 7)

4-IN.

2-IN. TO

5-IN.

(NOTE 6)

SIDE OVERLAP SEAM

- SOIL PREPARATION

(NOTE 1)

— EROSION CONTROL BLANKET

2-FT. —— '

-

 $\phi \vdash \phi \rightarrow \phi \vdash \phi$

HIGH FLOW CHANNEL

3.75 STAPLES PER SQ.YD

(NOTE 11)

ISOMETRIC VIEW

STAPLE PATTERNS

GENERAL NOTES

- 1. PREPARE SOIL BEFORE INSTALLING ROLLED EROSION CONTROL PRODUCTS (RECPS), INCLUDING ANY NECESSARY APPLICATION OF LIME, FERTILIZER, AND SEED.
- 2. BEGIN AT THE TOP OF THE CHANNEL BY ANCHORING THE RECPS IN A 6-INCH DEEP BY 6-IN. WIDE TRENCH WITH APPROXIMATELY 12-IN. OF RECPS EXTENDED BEYOND THE UP-SLOPE PORTION OF THE TRENCH. ANCHOR THE RECPS WITH A ROW OF STAPLES/STAKES APPROXIMATELY 12-IN. APART IN THE BOTTOM OF THE TRENCH. BACKFILL AND COMPACT THE TRENCH AFTER STAPLING. APPLY SEED TO THE COMPACTED SOIL AND FOLD THE REMAINING 12-IN. PORTION OF RECPS BACK OVER THE SEED AND COMPACTED SOIL. SECURE RECPS OVER COMPACTED SOIL WITH A ROW OF
- STAPLES/STAKES SPACED APPROXIMATELY 12-IN. APART ACROSS THE WIDTH OF THE RECPS. 3. ROLL CENTER RECPS IN DIRECTION OF WATER FLOW IN BOTTOM OF CHANNEL. RECPS WILL UNROLL WITH APPROPRIATE SIDE AGAINST THE SOIL SURFACE. ALL RECPS MUST BE SECURELY FASTENED TO SOIL SURFACE BY PLACING STAPLES/STAKES IN APPROPRIATE LOCATIONS AS SHOWN IN THE STAPLE
- 4. PLACE CONSECUTIVE RECPS END-OVER-END (SHINGLE STYLE) WITH A 4 TO 6-IN. OVERLAP. USE A DOUBLE ROW OF STAPLES STAGGERED 4-IN. APART AND 4-INCH ON CENTER TO SECURE RECPS. 5. FULL LENGTH EDGE OF RECPS AT TOP OF SIDE SLOPES MUST BE ANCHORED WITH A ROW OF
- STAPLES/STAKES APPROXIMATELY 12-IN. APART IN A 6-IN. DEEP X 6-IN. WIDE TRENCH. BACKFILL AND COMPACT THE TRENCH AFTER STAPLING. 6. ADJACENT RECPS MUST BE OVERLAPPED APPROXIMATELY 2-IN. TO 5-IN. (DEPENDING ON RECPS
- TYPE) AND STAPLED. 7. IN HIGH FLOW CHANNEL APPLICATIONS A STAPLE CHECK SLOT IS RECOMMENDED AT 30-FT. TO 40-FT. INTERVALS. USE A DOUBLE ROW OF STAPLES STAGGERED 4-IN. APART AND 4-IN. ON CENTER OVER ENTIRE WIDTH OF THE CHANNEL.
- 8. THE TERMINAL END OF THE RECPS MUST BE ANCHORED WITH A ROW OF STAPLES/STAKES APPROXIMATELY 12-IN. APART IN A 6-IN. DEEP BY 6-IN. WIDE TRENCH. BACKFILL AND COMPACT THE TRENCH AFTER STAPLING.
- 9. HORIZONTAL STAPLE SPACING SHOULD BE ALTERED IF NECESSARY TO ALLOW STAPLES TO SECURE THE CRITICAL POINTS ALONG THE CHANNEL SURFACE.
- NECESSARY TO PROPERLY SECURE THE RECP'S. 11. EROSION CONTROL BLANKETS SHALL BE NORTH AMERICAN GREEN OR ENGINEER APPROVED

10. IN LOOSE SOIL CONDITIONS, THE USE OF STAPLE OR STAKE LENGTHS GREATER THAN 6-IN. MAY BE


ALTERNATE. REFER TO PLAN VIEW DRAWINGS FOR NORTH AMERICAN GREEN'S PRODUCT NAME FOR

- SPECIFIC GRADE OF EROSION CONTROL BLANKET FOR EACH ROADSIDE SWALE/DITCH. 12. FOLLOW MANUFACTURERS SPECIFICATIONS IF THERE IS A DISCREPANCY IN NOTES OR IF ENGINEER
- APPROVED ALTERNATIVE IS USED.

MAINTENANCE NOTES

- 1. ALL SEDIMENT AND EROSION CONTROLS SHALL BE INSPECTED AT LEAST ONCE EVERY SEVEN CALENDAR DAYS AND AFTER ANY STORM EVENT OF GREATER THAN 0.5 INCHES OF PRECIPITATION DURING ANY 24-HOUR PERIOD. INSPECTIONS MUST BE CONDUCTED UNTIL FINAL STABILIZATION IS REACHED ON ALL AREAS OF THE CONSTRUCTION SITE.
- 2. GOOD CONTACT WITH THE GROUND MUST BE MAINTAINED, AND EROSION MUST NOT OCCUR 3. ANY AREAS OF THE RECP THAT ARE DAMAGED OR NOT IN CLOSE CONTACT WITH THE GROUND
- SHALL BE REPAIRED AND STAPLED.
- 4. IF EROSION OCCURS DUE TO POORLY CONTROLLED DRAINAGE, THE PROBLEM SHALL BE FIXED AND THE ERODED AREA PROTECTED.
- 5. MONITOR AND REPAIR THE RECP AS NECESSARY UNTIL GROUND COVER IS ESTABLISHED.
- REFERENCE: DETAIL BASED ON SCDHEC STORM WATER MANAGEMENT BMP HANDBOOK DATED JULY 31, 2015 (PORTIONS REVISED MAY 2014) AND NORTH AMERICAN GREEN INSTALLATION GUIDE.





S&ME, INC. **以** NO. C00473

2016 AYRSLEY TOWN BLVD.

SUITE 2-A

CHARLOTTE, NC 28273

(704) 523-4726

ENGINEERING FIRM

LICENSE NUMBER: F-0176


- 1. BASIN PREPARATIONS: PLACE TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES PER THE PLANS. CLEAR, GRUB AND STRIP TOPSOIL FROM THE EMBANKMENT TO REMOVE VEGETATION, STUMPS, ROOTS, ORGANIC MATERIAL, TRASH, ROCK MATERIAL AND OTHER OBJECTIONABLE MATERIAL. REMOVE SEDIMENT, PERVIOUS MATERIAL, ORGANIC MATERIAL TO THE DESIGN ELEVATION AND DIMENSIONS OF THE BASIN. KEEP BASIN DRY DURING CONSTRUCTION ACTIVITIES. THE FLOOR OF THE BASIN SHALL BE GRADED TO THE FINAL ELEVATION SHOWN ON THE DRAWINGS AND THE GRADED BASIN SHALL BE COMPACTED WITH A MINIMUM 10-TON SMOOTH DRUM (NON-VIBRATORY) COMPACTOR AND THEN PROOF-ROLLED. PROOF-ROLL THE ENTIRE SEDIMENTATION BASIN FLOOR. THE PROOF ROLLING SHALL BE OBSERVED AND EVALUATED BY THE ENGINEER OR HIS REPRESENTATIVE.
- 2. PRINCIPAL SPILLWAY, BARREL, AND SKIMMER: CONSTRUCT THE BARREL ACCORDING TO THE BELOW TEMPORARY SEDIMENT BASIN DETAIL. SECURE ALL CONNECTIONS BETWEEN BARREL AND RISER SECTIONS BY APPROVED WATERTIGHT ASSEMBLIES. ATTACH BASIN SKIMMER TO RISER BY APPROVED WATERTIGHT ASSEMBLIES (SEE SKIMMER DETAIL). DO NOT USE PERVIOUS MATERIAL SUCH AS SAND, GRAVEL, SILT, OR CRUSHED STONE AS BACKFILL MATERIAL AROUND THE PIPE. PLACE THE FILL MATERIAL AROUND THE PIPE SPILLWAY IN 4-IN. LOOSE LAYERS AND COMPACT IT AROUND THE PIPE TO 95 PERCENT OR GREATER AS THE REST OF THE EMBANKMENT FILL. CARE MUST BE TAKEN NOT TO RAISE THE PIPE FROM FIRM CONTACT WITH ITS FOUNDATION WHEN COMPACTING UNDER THE PIPE HAUNCHES. PLACE A MINIMUM DEPTH OF TWO FEET OF HAND COMPACTED BACKFILL OVER THE PIPE SPILLWAY BEFORE CROSSING THE PIPE WITH COMPACTION EQUIPMENT OR CONSTRUCTION EQUIPMENT.
- 3. EMBANKMENT CONSTRUCTION: USE CLEAN FILL MATERIAL BROUGHT TO SITE OR EXCAVATED FROM APPROVED AREAS ON SITE, IT SHALL BE CLEAN MINERAL SOIL, FREE OF ROOTS, WOODY VEGETATION, ROCKS AND OTHER OBJECTIONABLE MATERIAL SCARIFY AREAS AND EACH COMPACTED LIFT ON WHICH FILL IS TO BE PLACED BEFORE PLACING THE FILL. THE FILL OPTIMUM MOISTURE CONTENT SHALL BE MAINTAINED BETWEEN OPTIMUM AND THREE PERCENT ABOVE OPTIMUM. FILL SHALL BE COMPACTED NOT LESS THAN 95 PERCENT OF THE MAXIMUM DRY DENSITY AS DETERMINED BY ASTM D698 METHOD A. THE CONTRACTOR SHALL DEMONSTRATE SOIL DENSITY BY SOIL COMPACTION PER THE PLANS AND SPECIFICATIONS WITH A MINIMUM OF TWO DENSITY TESTS PER LIFT WITH TESTS SPACED EVENLY AND REPRESENTATIVE OF THE EMBANKMENT FILL. ONE FAILED TEST REQUIRES THAT THE LIFT BE RE-COMPACTED AND RE-TESTED AT TWO LOCATIONS UNTIL REQUIRED COMPACTION IS ACHIEVED. NO VEGETATIVE COVER MATERIAL SHALL BE PLACED ON COMPACTED FILL LAYERS BEFORE THE ENGINEER REVIEWS AND APPROVES THE DENSITY DATA FROM THE TESTING PERFORMED. THE ENGINEER MAY EVALUATE COMPACTION AND REPORT THE RESULTS TO THE CONTRACTOR. FAILED SOIL DENSITY TESTS PERFORMED BY THE ENGINEER WILL REQUIRE THAT THE COMPACTED MATERIAL BE REMOVED AND RE-INSTALLED PER THE PLANS AND SPECIFICATIONS.
- 4. OUTLET DISCHARGE: EFFLUENT FROM THE PRINCIPAL SPILLWAY BARREL FROM THE SEDIMENT BASIN SHALL HAVE AN SEEPAGE DIAPHRAGM DRAIN AND SHALL DISCHARGE TO A PLUNGE POOL (SEE DETAIL).
- 5. EMERGENCY SPILLWAY: INSTALL THE EMERGENCY SPILLWAY IN THE UNDISTURBED SOIL. TOLERANCE TO DESIGN ELEVATIONS IS +/- 0.2 FEET; TOLERANCE TO DESIGN GRADES IS +/- 1.0 PERCENT; AND TOLERANCE FOR WIDTHS AND LENGTHS IS +/- 1.0-FT NO DEVIATION FROM THE SPECIFIED TOLERANCES SHALL BE ALLOWED, LINE THE SPILLWAY WITH LAMINATED PLASTIC OR IMPERMEABLE GEOTEXTILE FABRIC. THE FABRIC SHALL HAVE DIMENSIONS LARGE ENOUGH TO COVER THE BOTTOM AND SIDES AND EXTEND ONTO THE TOP OF THE DAM FOR ANCHORING IN A TRENCH. THE EDGES SHALL BE SECURED WITH 8-IN. STAPLES OR PINS. THE FABRIC MUST BE LONG ENOUGH TO EXTEND DOWN THE SLOPE AND EXIT ONTO STABLE GROUND. THE WIDTH OF THE FABRIC SHALL BE ONE PIECE, TO PREVENT WATER FROM ACCESS BENEATH THE FABRIC; JOINING OR SPLICING OF SECTIONS ACROSS THE WIDTH SHALL NOT BE ALLOWED. THE LENGTH OF THE FABRIC MAY BE COMPOSED OF SECTIONS SPANNING THE ENTIRE SPILLWAY WIDTH. UPPER SECTIONS SHALL OVERLAP LOWER SECTIONS SO THAT WATER CANNOT FLOW UNDER THE FABRIC. SECURE THE UPPER EDGE AND SIDES OF THE FABRIC IN A TRENCH WITH STAPLES OR PINS (ADAPTED FROM "A MANUAL FOR DESIGNING INSTALLING AND MAINTAINING SKIMMER SEDIMENT BASINS" FEBRUARY, 1999 J.W. FAIRCLOTH & SON). A 6-IN. VEGETATIVE COVER SHALL BE PLACED ON TOP OF THE GEOTEXTILE FABRIC. EROSION CONTROL MATTING SHALL BE PLACED ON TOP OF THE VEGETATIVE LAYER.
- 6. INLETS: INSTALL INLETS TO DISCHARGE WATER INTO THE FOREBAYS IN A MANNER TO PREVENT EROSION.
- 7. EROSION CONTROL: CONSTRUCT THE STRUCTURE SO THAT THE DISTURBED AREA IS MINIMIZED. DIVERT SURFACE WATER AWAY FROM THE BARE AREAS. COMPLETE THE EMBANKMENT BEFORE ADDITIONAL UPSTREAM AREA IS CLEARED. STABILIZE THE EMERGENCY SPILLWAY EMBANKMENT AND ALL OTHER DISTURBED AREAS ABOVE THE CREST OF THE PRINCIPAL SPILLWAY IMMEDIATELY AFTER CONSTRUCTION (REFERENCES: SURFACE STABILIZATION).

MAINTENANCE:

- 1. CHECK SEDIMENT BASIN AFTER PERIODS OF SIGNIFICANT RUNOFF. REMOVE SEDIMENT AND RESTORE THE BASIN TO ITS ORIGINAL DIMENSIONS WHEN SEDIMENT ACCUMULATES TO ONE-HALF THE DESIGN DEPTH AS MARKED BY THE SEDIMENT CLEANOUT STAKE.
- 2. CHECK THE EMBANKMENT, SPILLWAYS AND OUTLET FOR EROSION DAMAGE AND EVALUATE THE EMBANKMENT FOR PIPING AND SETTLEMENT. MAKE ALL NECESSARY REPAIRS IMMEDIATELY. REMOVE ALL TRASH AND DEBRIS FROM THE RISER AND POOL
- 3. ALL SEDIMENT AND EROSION CONTROLS SHALL BE INSPECTED AT LEAST ONCE EVERY SEVEN CALENDAR DAYS AND AFTER ANY STORM EVENT OF GREATER THAN 0.5 INCHES OF PRECIPITATION DURING ANY 24-HOUR PERIOD. INSPECTIONS MUST BE CONDUCTED UNTIL FINAL STABILIZATION IS REACHED ON ALL AREAS OF THE CONSTRUCTION SITE. REMOVE SEDIMENT AND RESTORE THE BASIN TO ITS ORIGINAL DIMENSIONS WHEN SEDIMENT ACCUMULATES TO ONE-HALF THE HEIGHT OF THE BASIN DEPTH. FIRST PULL THE SKIMMER TO ONE SIDE TO ACCESS SEDIMENT BELOW FOR REMOVAL. EXCAVATE THE SEDIMENT FROM THE ENTIRE BASIN, NOT LIMITED TO THE SKIMMER LOCATION OR WITHIN THE FIRST BASIN CELL. CUT OR REMOVE VEGETATION FROM THE BOTTOM OF THE BASIN THAT LIMITS OPERATION OF THE SKIMMER OR RESTRICTS ITS ABILITY TO FLOAT.

4. REPAIR DAMAGED BAFFLES. RE-ANCHOR BAFFLES IF WATER IS FLOWING UNDERNEATH OR AROUND THEM.

- 5. REMOVE CLOGS FROM SKIMMER BY JERKING ON THE ROPE TO BOB THE SKIMMER, OR PULL THE SKIMMER TO ONE SIDE OF THE BASIN AND REMOVE THE DEBRIS. CHECK THE ORIFICE INSIDE THE SKIMMER FOR DEBRIS. IF PRESENT, REMOVE THE DEBRIS. IF THE SKIMMER ARM OR BARREL IS CLOGGED, REMOVE THE ORIFICE AND FLUSH WITH WATER TO RESTORE FLOW, OR USE A PLUMBERS SNAKE TO REMOVE THE CLOG. REPLACE THE ORIFICE BEFORE REPOSITIONING THE SKIMMER.
- 6. CHECK THE FABRIC LINED SPILLWAY FOR DAMAGE AND MAKE REQUIRED REPAIRS WITH FABRIC THAT SPANS THE FULL WIDTH OF THE SPILLWAY. CHECK THE EMBANKMENT, SPILLWAYS, AND OUTLET FOR EROSION DAMAGE, AND INSPECT THE EMBANKMENT FOR PIPING AND SETTLEMENT. MAKE NECESSARY REPAIRS IMMEDIATELY. REMOVE ALL TRASH AND OTHER DEBRIS FROM THE SKIMMER, RISER, AND POOL AREAS.
- 7. FREEZING WEATHER CAN RESULT IN ICE FORMING IN THE BASIN. PREVENT ICE FROM CLOGGING THE SKIMMER.



- 1. ASSEMBLE THE SKIMMER AS DESIGNED (PER THE SKIMMER DETAIL).
- 2. LAY THE ASSEMBLED SKIMMER ON THE BOTTOM OF THE BASIN. SECURE THE CONNECTIONS BETWEEN THE INLET BASIN SKIMMER FLEXIBLE JOINT TO THE RISER ORIFICE BY APPROVED WATERTIGHT ASSEMBLIES. POSITION THE SKIMMER OVER THE SUPPORT PAD. ATTACH A ROPE TO THE SKIMMER AND ANCHOR IT TO THE SIDE OF THE BASIN FOR ACCESS TO THE SKIMMER FOR FUTURE MAINTENANCE.


POST-CONSTRUCTION SPECIFICATIONS


- WHEN THE AREAS CONTRIBUTING SEDIMENT TO THE SYSTEM HAVE BEEN STABILIZED, PROCEDURES CAN BE TAKEN TO RESTORE THE SYSTEM TO ITS PERMANENT USE. THE FOLLOWING REMOVAL AND RESTORATION PROCEDURE IS RECOMMENDED. DURING THIS PROCESS CAREFUL CONSIDERATION SHOULD BE TAKEN TO PROTECT RECEIVING WATERS FROM SEDIMENT POLLUTION AND EROSION DAMAGE.
- 1. REMOVE EROSION AND SEDIMENT CONTROL DEVICES (SKIMMER, BAFFLES, 30 MIL LINER, AND STAINLESS STEEL STRAP).
- 2. EXCAVATE THE BASIN TO THE ORIGINAL PROPOSED BOTTOM OF BASIN ELEVATION PER THE PLANS TO REMOVE ANY ACCUMULATED SEDIMENT. MAINTAIN THE DESIGNED SIDE SLOPES AND APPLY SLOPE MATTING PER THE DETAIL.
- 3. INSTALL RIPRAP BERM (SCDOT CLASS A RIPRAP), AT MINIMUM 5-FT AWAY FROM RISER. RIPRAP BERM IS TO BE USED TO HELP PREVENT THE RISER ORIFICE FROM CLOGGING. SEE DETAIL FOR SIZE AND GEOMETRY OF BERM.
- 4. STABILIZE THE BASIN AND ANY AREAS DISTURBED DURING EROSION AND SEDIMENT CONTROL DEVICE AND SEDIMENT REMOVAL


SEDIMENT BASIN SUMMARY TABLE														
	Α	В	С	D	E	F	G	Н	I	J	K	L	M	N
SEDIMENT BASIN ID	BOTTOM OF BASIN ELEVATION (FT.)	TOP OF RISER ELEVATION (FT.)	EMERGENCY SPILLWAY CREST ELEVATION (FT.)	TOP OF BERM ELEVATION (FT.)	TOP OF BERM WIDTH (FT.)	CLEAN OUT ELEVATION (FT.)	RISER SHAPE (FT. X FT.)	OUTLET PIPE DIAMETER (DO) (FT.)	OUTLET PIPE UPSTREAM INV. ELEVATION (FT.)	OUTLET PIPE DOWNSTREAM INV. ELEVATION (FT.)	LENGTH OF OUTLET PIPE (FT.)	SLOPE OF OUTLET PIPE (%)	INTERIOR SIDE SLOPES (Z FT. X 1 FT.)	EMERGENCY SPILLWAY INTERIOR SIDE SLOPES (Z FT. X 1 FT.)

THE SEDIMENT BASIN SUMMARY TABLE WILL BE POPULATED FOLLOWING THE DETAILED DESIGN.










ADDITIONAL PRECAST DESIGN REQUIREMENTS:

1. RISER SHALL BE DESIGNED FOR A WATER PRESSURE OF 1,300 PSF AND HORIZONTAL SOIL PRESSURE OF 700 PSF. (TOTAL HORIZONTAL PRESSURE OF 2,000 PSF).

GENERAL DESIGN NOTES

- STRENGTH DESIGN METHOD IN ACCORDANCE WITH (I.A.W.) ACI318.
- 2. APPLICABLE DESIGN DOCUMENTS(CURRENT EDITIONS):
- ACI318 BUILDING CODE REQUIREMENTS FOR STRUCTURAL CONCRETE (MAIN DESIGN SPECIFICATIONS).
- ASTM C890 STANDARD PRACTICE FOR MINIMUM STRUCTURAL LOADING FOR MONOLITHIC OR SECTIONAL PRECAST CONCRETE WATER AND WASTEWATER
- STRUCTURES (LOADING SPECIFICATIONS). • ASTM C913 STANDARD SPECIFICATIONS FOR PRECAST CONCRETE AND WATER AND WASTEWATER STRUCTURES.
- 3. MAX DEPTH TO INVERT OF PRECAST (I.E. FLOOR) =15' FOR SOLID BASE AND 10 FOR WAFFLE
- 4. GROUNDWATER TABLE ASSUMED TO BE BELOW THE INVERT OF THE OUTLET PIPE.
- 5. LATERAL DESIGN PRESSURES (AS APPLICABLE TO DESIGN): • EQUIV DRY SOIL FLUID PRESSURE =47 PCF.
- EQUIV SATURATED SOIL FLUID PRESSURE =85 PCF.
- LIVE LOAD SURCHARGE =80 PSF. DESIGN CONCRETE COMPRESSIVE STRENGTH AT 28 DAYS =4,000 PSI (MIN.)
- 7. REINFORCEMENT: • CARBON-STEEL DEFORMED BARS: ASTM A615, fy =60 KSI (MIN.)
- WELDED WIRE REINFORCEMENT (DEFORMED): ASTM A1064 fy =70 KSI (MIN.)
- 8. COPOLYMER POLY PROPYLENE STEEL REINFORCED STEPS I.A.W. ASTM C478 SPACED 16" O.C. LIFT LOOPS, PINS OR UTILITY ANCHORS PROVIDED FOR HANDLING. CONTRACTOR SHALL BE RESPONSIBLE FOR FOLLOWING OLD CASTLE PRECAST, INC. LIFTING INSTRUCTIONS AS SHOWN ON BACK OF SHIPPING TICKET.



THE CONCRETE RISER SUMMARY TABLE WILL BE POPULATED FOLLOWING THE DETAILED DESIGN.



2016 AYRSLEY TOWN BLVD. SUITE 2-A CHARLOTTE, NC 28273 (704) 523-4726

ENGINEERING FIRM

LICENSE NUMBER: F-0176



PROJECT NUMBER 22350640 DRAWING NUMBER


PERSPECTIVE VIEW

DIMENSIONS WHEN SEDIMENT ACCUMULATES TO ONE-HALF THE HEIGHT OF THE POOL. CHECK EMBANKMENT, LINING, AND OUTLET


PLUNGE POOL SIZING SUMMARY TABLE

THE PLUNGE POOL SUMMARY TABLE WILL BE POPULATED FOLLOWING THE DETAILED DESIGN.

AREA FOR ANY DAMAGE AND REPAIR AS NECESSARY, AS SOON AS PRACTICAL.



FLAT BOTTOM TRENCH DETAIL



V-SHAPED TRENCH DETAIL

BAFFLES - POST REQUIREMENTS:

- 1. POROUS BAFFLE POSTS MUST BE 60-IN. TO 96-IN. LONG STEEL POSTS THAT MEET, AT A MINIMUM, THE FOLLOWING PHYSICAL CHARACTERISTICS.
- COMPOSED OF A HIGH STRENGTH STEEL WITH A MINIMUM YIELD STRENGTH OF 50,000 PSI.
- INCLUDE A STANDARD "T" SECTION WITH A NOMINAL FACE WIDTH OF 1.38-IN. AND A NOMINAL "T" LENGTH
- OF 1.48-IN.

 WEIGH 1.25 POUNDS PER FOOT (± 8%).
- 2. POSTS SHALL BE EQUIPPED WITH PROJECTIONS TO AID IN FASTENING OF BAFFLE MATERIAL.
- 3. INSTALL POSTS TO A MINIMUM OF 24-IN. A MINIMUM HEIGHT OF 1-IN. TO 2-IN. ABOVE THE FABRIC SHALL BE MAINTAINED, AND A MAXIMUM HEIGHT OF 3-FT. SHALL BE MAINTAINED ABOVE THE GROUND.
- 4. POST SPACING SHALL BE AT A MAXIMUM OF 4-FT. ON CENTER.

BAFFLES - MATERIAL REQUIREMENTS:

- 1. BAFFLE MATERIAL MUST BE COMPOSED OF COIR-BASED MATERIALS OR TURF REINFORCEMENT MATTING (TRM) THAT CONSISTS OF THE FOLLOWING REQUIREMENTS:
- HAVE A LIGHT PENETRATION (% OPENINGS) BETWEEN 10-35%;
- FREE OF LOOSE STRAW MATERIAL;
- HAVE A MINIMUM TENSILE STRENGTH OF 145 LB/FT; AND,
- HAVE A MINIMUM WIDTH OF 48-IN.
- 2. 12-IN. OF THE FABRIC SHOULD BE PLACED WITHIN THE EXCAVATED TRENCH AND TOED IN WHEN THE TRENCH IS BACKFILLED OR BAFFLE MATERIAL MAY BE STAPLED INTO
- 3. BAFFLE MATERIAL SHALL BE PURCHASED IN CONTINUOUS ROLLS AND CUT TO THE WIDTH OF THE SEDIMENT BASIN OR TRAP TO AVOID JOINTS.

GROUND BY USING 12-IN. STAPLES WITH A MAXIMUM

BAFFLES - GENERAL NOTES:

SPACING OF 12-IN.

- 4. ATTACH BAFFLE TO THE STEEL POSTS USING HEAVY-DUTY PLASTIC TIES THAT ARE EVENLY SPACED ALONG THE ABOVE GROUND PORTION OF EACH POST.
- 5. INSTALL THE BAFFLE ROWS PERPENDICULAR TO THE DIRECTION OF THE STORMWATER FLOW AND PLACE EACH BAFFLE THE PROPER DISTANCE FROM INLET AND OUTLETS TO ALLOW ACCESS FOR MAINTENANCE AND CLEAN-OUT AS PER THE PLANS.
- 6. EXTEND BAFFLE TO A MINIMUM OF 3 FEET IN HEIGHT.

- BAFFLES INSPECTION & MAINTENANCE:

 1. THE KEY TO FUNCTIONAL POROUS BAFFLES IS WEEKLY INSPECTION, ROUTINE MAINTENANCE, AND REGULAR SEDIMENT REMOVAL.
- 2. ALL SEDIMENT AND EROSION CONTROLS SHALL BE INSPECTED AT LEAST ONCE EVERY SEVEN CALENDAR DAYS AND AFTER ANY STORM EVENT OF GREATER THAN 0.5 INCHES OF PRECIPITATION DURING ANY 24-HOUR PERIOD. INSPECTIONS MUST BE CONDUCTED UNTIL FINAL STABILIZATION IS REACHED ON ALL AREAS OF THE CONSTRUCTION SITE.

2016 ARSLEY TOWN BLVD

SUITE 2-A

CHARLOTTE, NC 28273

(704) 523-4726

ENGINEERING FIRM

LICENSE NUMBER: F-0176

S&ME, INC.

ا No. C00473

PROJECT NUMBER

22350640


DRAWING NUMBER


- 3. ATTENTION TO SEDIMENT ACCUMULATIONS ALONG EACH ROW OF BAFFLES IS EXTREMELY IMPORTANT. ACCUMULATED SEDIMENT SHOULD BE CONTINUALLY MONITORED AND REMOVED WHEN NECESSARY.
- 4. REMOVE ACCUMULATED SEDIMENT WHEN IT REACHES 1/3 THE HEIGHT OF THE BAFFLE ROW OR WHEN IT REACHES THE CLEAN-OUT HEIGHT OF THE SEDIMENT BASIN OR TRAP, WHICHEVER IS REACHED FIRST.
- 5. REMOVED SEDIMENT SHALL BE PLACED IN STOCKPILE STORAGE AREAS OR SPREAD THINLY ACROSS DISTURBED AREA. STABILIZE THE REMOVED SEDIMENT AFTER IT IS
- RELOCATED.

 6. CHECK FOR AREAS WHERE STORMWATER RUNOFF HAS ERODED A CHANNEL BENEATH EACH ROW OF BAFFLES, OR WHERE THE BAFFLE HAS SAGGED OR COLLAPSED DUE
- TO RUNOFF OVERTOPPING THE BAFFLE.

 7. CHECK FOR TEARS/RIPS WITHIN THE BAFFLES, AREAS WHERE THE BAFFLE HAS BEGUN TO DECOMPOSE, AND FOR ANY OTHER CIRCUMSTANCE THAT MAY RENDER THE BAFFLE INEFFECTIVE. REMOVED DAMAGED BAFFLES AND REINSTALL NEW BAFFLES IMMEDIATELY.
- 8. POROUS BAFFLES SHOULD BE REMOVED WITHIN 30 DAYS AFTER FINAL STABILIZATION IS ACHIEVED AND ONCE IT IS REMOVED, THE RESULTING DISTURBED AREA SHALL BE PERMANENTLY STABILIZED.
- REMOVE ANY ACCUMULATED SEDIMENT UPON BAFFLE REMOVAL. DISPOSE OF SEDIMENT OFF-SITE ACCORDING TO STATE AND LOCAL REGULATIONS.







CONDUCTED UNTIL FINAL STABILIZATION IS REACHED ON ALL AREAS OF THE

CONSTRUCTION SITE.

DRAWING PATH: T.\Charlotte-1350\Projects\2022\22350640_Luck Co_Luck Stone Edgefield Mine Site_Winnsboro SC\4 Energy\CAD\DWG\MINING SWPPP\DETAILS (SHEET 3 OF 9).dw

PROFILE VIEW

GENERAL NOTES

- 1. DO NOT PLACE SILT FENCE ACROSS CHANNELS OR IN OTHER AREAS SUBJECT TO CONCENTRATED FLOWS. SILT FENCE SHOULD NOT BE USED AS A VELOCITY CONTROL BMP. CONCENTRATED FLOWS ARE ANY FLOWS GREATER THAN 0.5 CFS.
- 2. MAXIMUM SHEET OR OVERLAND FLOW PATH LENGTH TO THE SILT FENCE SHALL BE 100-FT..
- 3. MAXIMUM SLOPE STEEPNESS (NORMAL
- [PERPENDICULAR] TO THE FENCE LINE) SHALL BE 2:1. 4. SILT FENCE JOINTS, WHEN NECESSARY, SHALL BE
- COMPLETED BY ONE OF THE FOLLOWING OPTIONS: 4.1. WRAP EACH FABRIC TOGETHER AT A SUPPORT POST 3. EACH POST TO BE EQUIPPED WITH SAFETY CAP. WITH BOTH ENDS FASTENED TO THE POST, WITH A 4. STEEL POSTS MAY NEED TO HAVE A METAL SOIL 1-FOOT MINIMUM OVERLAP;
- 4.2. OVERLAP SILT FENCE BY INSTALLING 3-FT. PAST THE SUPPORT POST TO WHICH THE NEW SILT FENCE ROLL IS ATTACHED. ATTACH OLD ROLL TO NEW
- ROLL WITH HEAVY-DUTY PLASTIC TIES; OR, 4.3. OVERLAP ENTIRE WIDTH OF EACH SILT FENCE ROLL FROM ONE SUPPORT POST TO THE NEXT SUPPORT
- 5. ATTACH FILTER FABRIC TO THE STEEL POSTS USING HEAVY-DUTY PLASTIC TIES THAT ARE EVENLY SPACED
- 6. INSTALL THE SILT FENCE PERPENDICULAR TO THE DIRECTION OF THE STORMWATER FLOW AND PLACE THE SILT FENCE THE PROPER DISTANCE FROM THE TOE

OF STEEP SLOPES TO PROVIDE SEDIMENT STORAGE

WITHIN THE TOP 8-IN. OF THE FABRIC.

AND ACCESS FOR MAINTENANCE AND CLEANOUT. 7. INSTALL SILT FENCE CHECKS (TIE-BACKS) EVERY 50-100 -FT., DEPENDENT ON SLOPE, ALONG SILT FENCE THAT IS INSTALLED WITH SLOPE AND WHERE CONCENTRATED FLOWS ARE EXPECTED OR ARE DOCUMENTED ALONG THE PROPOSED/INSTALLED SILT FENCE.

POST REQUIREMENTS

- 1. SILT FENCE POSTS MUST BE 5-FT. LONG STEEL POSTS THAT MEET, AT A MINIMUM, THE FOLLOWING PHYSICAL CHARACTERISTICS.
- 1.1. COMPOSED OF A HIGH STRENGTH STEEL WITH A MINIMUM YIELD STRENGTH OF 50,000 PSI. 1.2. INCLUDE A STANDARD "T" SECTION WITH A NOMINAL FACE WIDTH OF 1.38-IN. AND A
- NOMINAL "I" LENGTH OF 1.48-IN. 1.3. WEIGH 1.25 POUNDS PER FOOT (± 8%)
- 2. POSTS SHALL BE EQUIPPED WITH PROJECTIONS TO AID IN FASTENING OF FILTER FABRIC.
- STABILIZATION PLATE WELDED NEAR THE BOTTOM WHEN INSTALLED ALONG STEEP SLOPES OR INSTALLED IN LOOSE SOILS. THE PLATE SHOULD HAVE A MINIMUM CROSS SECTION OF 17-SQUARE -IN. AND BE COMPOSED OF 15 GAUGE STEEL, AT A

MINIMUM. THE METAL SOIL STABILIZATION PLATE

- SHOULD BE COMPLETELY BURIED. 5. INSTALL POSTS TO A MINIMUM DEPTH OF 24-IN. A MINIMUM HEIGHT OF 1-IN. TO 2-IN. ABOVE THE FABRIC SHALL BE MAINTAINED, AND A MAXIMUM HEIGHT OF 3-FT. SHALL BE MAINTAINED ABOVE THE
- 6. POST SPACING SHALL BE AT A MAXIMUM OF 6-FT. ON CENTER.
- 7. WOODEN POSTS ARE ALLOWED WHEN CROSSING UTILITIES. OWNER'S DESIGNATED ENVIRONMENTAL REPRESENTATIVE SHALL APPROVE LOCATIONS WHERE WOODEN POST ARE TO BE USED PRIOR TO INSTALLATION.

- **FABRIC REQUIREMENTS** 1. SILT FENCE MUST BE COMPOSED OF WOVEN GEOTEXTILE FILTER FABRIC THAT CONSISTS OF THE
- FOLLOWING REQUIREMENTS: 1.1. COMPOSED OF FIBERS CONSISTING OF LONG CHAIN SYNTHETIC POLYMERS OF AT LEAST 85% BY WEIGHT OF POLYOLEFINS, POLYESTERS, OR POLYAMIDES THAT ARE FORMED INTO A NETWORK SUCH THAT THE FILAMENTS OR YARNS

RETAIN DIMENSIONAL STABILITY RELATIVE TO

- EACH OTHER; 1.2. FREE OF ANY TREATMENT OR COATING WHICH MIGHT ADVERSELY ALTER ITS PHYSICAL
- PROPERTIES AFTER INSTALLATION; 1.3. FREE OF ANY DEFECTS OR FLAWS THAT SIGNIFICANTLY AFFECT ITS PHYSICAL AND/OR
- FILTERING PROPERTIES; AND, 1.4. HAVE A MINIMUM WIDTH OF 36-IN. 2. USE ONLY FABRIC APPEARING ON SC DOT'S QUALIFIED PRODUCTS LISTING (QPL), APPROVAL SHEET #34, MEETING THE REQUIREMENTS OF THE
- MOST CURRENT EDITION OF THE SC DOT STANDARD SPECIFICATIONS FOR HIGHWAY CONSTRUCTION. 3. 12-IN. OF THE FABRIC SHOULD BE PLACED WITHIN EXCAVATED TRENCH AND SECURED WHEN THE
- TRENCH IS BACKFILLED. 4. FILTER FABRIC SHALL BE PURCHASED IN CONTINUOUS ROLLS AND CUT TO THE LENGTH OF
- THE BARRIER TO AVOID JOINTS. 5. FILTER FABRIC SHALL BE INSTALLED AT A MINIMUM OF 24-IN. ABOVE THE GROUND.

SECTION VIEW

5-FT. STEEL POST —

HEAVY DUTY -

PLASTIC TIES

COMPACTED -

BACKFILL

FLOW

FILTER FABRIC -

6-IN.

BURY FILTER FABRIC -


INSPECTION & MAINTENANCE

24-IN.


MIN.


- 1. THE KEY TO FUNCTIONAL SILT FENCE IS WEEKLY INSPECTIONS, ROUTINE MAINTENANCE, AND REGULAR SEDIMENT REMOVAL.
- 2. ALL SEDIMENT AND EROSION CONTROLS SHALL BE INSPECTED AT LEAST ONCE EVERY SEVEN CALENDAR DAYS AND AFTER ANY STORM EVENT OF GREATER THAN 0.5 INCHES OF PRECIPITATION DURING ANY 24-HOUR PERIOD. INSPECTIONS MUST BE CONDUCTED UNTIL FINAL STABILIZATION IS REACHED ON ALL AREAS OF THE CONSTRUCTION
- 3. ATTENTION TO SEDIMENT ACCUMULATIONS ALONG THE SILT FENCE IS EXTREMELY IMPORTANT. ACCUMULATED SEDIMENT SHOULD BE
- CONTINUALLY MONITORED AND REMOVED WHEN NECESSARY. 4. REMOVE ACCUMULATED SEDIMENT WHEN IT REACHES 1/3 THE HEIGHT OF
- 5. REMOVED SEDIMENT SHALL BE PLACED IN STOCKPILE STORAGE AREAS OR SPREAD THINLY ACROSS DISTURBED AREA. STABILIZE THE REMOVED SEDIMENT AFTER IT IS RELOCATED.
- 6. CHECK FOR AREAS WHERE STORMWATER RUNOFF HAS ERODED A CHANNEL BENEATH THE SILT FENCE, OR WHERE THE FENCE HAS SAGGED OR COLLAPSED DUE TO RUNOFF OVERTOPPING THE SILT FENCE. INSTALL CHECKS/TIE-BACKS AND/OR REINSTALL SILT FENCE, AS NECESSARY.
- 7. CHECK FOR TEARS WITHIN THE SILT FENCE, AREAS WHERE SILT FENCE HAS BEGUN TO DECOMPOSE, AND FOR ANY OTHER CIRCUMSTANCE THAT MAY RENDER THE SILT FENCE INEFFECTIVE. REMOVE DAMAGED SILT FENCE AND REINSTALL NEW SILT FENCE IMMEDIATELY.
- 8. SILT FENCE SHOULD BE REMOVED WITHIN 30 DAYS AFTER FINAL STABILIZATION IS ACHIEVED AND ONCE IT IS REMOVED, THE RESULTING DISTURBED AREA SHALL BE PERMANENTLY STABILIZED.


REFERENCE: DETAIL BASED ON SCDHEC STORM WATER MANAGEMENT BMP HANDBOOK DATED JULY 31, 2005, REVISED MARCH 2014.



SINGLE SOCK PLAN VIEW







SINGLE SOCK SECTION VIEW


GENERAL NOTES

- 1. USE FILTREXX® SILTSOXX™ ORIGINAL OR ENGINEER APPROVED ALTERNATIVE. COMPOST FILTER SOCK DIAMETER VARIES, REFER TO PLAN VIEW DRAWINGS FOR DIAMETER.
- 2. COMPOST FILTER SOCKS SHOULD BE LOCATED AS SHOWN ON PLANS AND AS DIRECTED BY THE OWNER'S DESIGNATED ENVIRONMENTAL REPRESENTATIVE.
- 3. PRIOR TO INSTALLATION, CLEAR ALL OBSTRUCTIONS INCLUDING ROCKS, CLODS, AND OTHER DEBRIS GREATER THAN 1-IN. THAT MAY INTERFERE WITH PROPER FUNCTION OF THE COMPOST
- 4. OAK OR OTHER DURABLE HARDWOOD STAKES 2-IN. BY 2-IN. IN CROSS SECTION SHOULD BE DRIVEN VERTICALLY PLUMB, THROUGH THE CENTER OF THE COMPOST FILTER SOCK. STAKES SHOULD BE PLACED AT A MAXIMUM INTERVAL OF 10-FT. O.C. STAKES SHOULD BE DRIVEN TO A MINIMUM DEPTH OF 12-IN., WITH A MINIMUM OF 3-IN. PROTRUDING ABOVE THE COMPOST
- FILTER SOCK. 5. WHERE APPLICABLE PLASTIC OR WIRE TIES SHALL HAVE MINIMUM 50-LB. TENSILE STRENGTH.
- 6. IN THE EVENT STAKING IS NOT POSSIBLE (HIGHLY COMPACTED SOILS OR IMPERVIOUS SURFACES) SAND BAGS OR HEAVY CONCRETE BLOCKS MAY BE USED BEHIND THE SOCK TO HOLD IT IN PLACE DURING RUNOFF EVENTS.
- 7. STRAIGHTEN OR POSITION THE COMPOST FILTER SOCK AS NEEDED ON THE GROUND, ENSURING THERE IS GOOD GROUND CONTACT AND NO VOID SPACES UNDER THE COMPOST FILTER SOCK.
- 8. DO NOT DRAG COMPOST FILTER SOCK ACROSS ROUGH SURFACES. IF DRAGGING ACROSS A ROUGH SURFACE IS NECESSARY, PLACE A BARRIER SUCH AS PLASTIC OR A TARP UNDER COMPOST FILTER SOCK TO PREVENT TEARING.
- 9. BACKFILL LOOSE COMPOST OR FINE WOOD CHIPS TO 1/2 THE HEIGHT OF THE COMPOST FILTER SOCK ALONG THE UPSLOPE SIDE, FILLING THE SEAM BETWEEN THE SOIL SURFACE AND THE
- COMPOST FILTER SOCK. 10. IF THE COMPOST FILTER SOCK IS TO BE LEFT AS PART OF THE NATURAL LANDSCAPE, IT MAY BE
- SEEDED WITH THE PERMANENT SEED MIX AT TIME OF INSTALLATION.
- 11. FOLLOW MANUFACTURERS SPECIFICATIONS IF THERE IS A DISCREPANCY IN NOTES OR IF ENGINEER APPROVED ALTERNATIVE IS USED.

MAINTENANCE NOTES

- 1. ALL SEDIMENT AND EROSION CONTROLS SHALL BE INSPECTED AT LEAST ONCE EVERY SEVEN CALENDAR DAYS AND AFTER ANY STORM EVENT OF GREATER THAN 0.5 INCHES OF PRECIPITATION DURING ANY 24-HOUR PERIOD. INSPECTIONS MUST BE CONDUCTED UNTIL FINAL STABILIZATION IS REACHED ON ALL AREAS OF THE CONSTRUCTION SITE. 2. MAKE ANY NECESSARY REPAIRS IMMEDIATELY.
- 3. THE MAXIMUM ALLOWABLE ACCUMULATED SEDIMENT IS 1/3 THE HEIGHT OF THE COMPOST FILTER SOCK. HOWEVER, ACCUMULATED SEDIMENT SHOULD BE REMOVED MORE FREQUENTLY. ALTERNATIVELY, A NEW COMPOST FILTER SOCK CAN BE PLACED ON TOP OF AND SLIGHTLY BEHIND
- THE ORIGINAL ONE CREATING MORE SEDIMENT STORAGE CAPACITY WITHOUT SOIL DISTURBANCE. 4. REMOVE ACCUMULATED SEDIMENT TO PROVIDE ADEQUATE STORAGE VOLUME FOR THE NEXT RAIN. TAKE CARE TO AVOID UNDERMINING THE COMPOST FILTER SOCK DURING CLEANOUT. 5. THE COMPOST SOCK MUST BE REPLACED IF CLOGGED OR TORN.
- 6. IF PONDING BECOMES EXCESSIVE, THE COMPOST FILTER SOCK MAY NEED TO BE REPLACED WITH ONE OF A LARGER DIAMETER OR A DIFFERENT MEASURE.
- 7. THE COMPOST FILTER SOCK NEEDS TO BE REINSTALLED IF UNDERMINED OR DISLODGED. 8. THE COMPOST FILTER SOCK SHALL BE MAINTAINED UNTIL DISTURBED AREA ABOVE THE DEVICE HAS
- BEEN PERMANENTLY STABILIZED AND CONSTRUCTION ACTIVITY HAS CEASED.





PROFILE VIEW

GENERAL NOTES

- 1. DO NOT PLACE SILT FENCE ACROSS CHANNELS OR IN OTHER AREAS SUBJECT TO CONCENTRATED FLOWS. SILT FENCE SHOULD NOT BE USED AS A VELOCITY CONTROL BMP. CONCENTRATED FLOWS ARE ANY FLOWS GREATER THAN 0.5 CFS.
- 2. MAXIMUM SHEET OR OVERLAND FLOW PATH LENGTH TO THE SILT FENCE SHALL BE 100-FT.
- 3. MAXIMUM SLOPE STEEPNESS (NORMAL [PERPENDICULAR]
- TO THE FENCE LINE) SHALL BE 2:1. 4. SILT FENCE JOINTS, WHEN NECESSARY, SHALL BE COMPLETED BY ONE OF THE FOLLOWING OPTIONS:
- 4.1. WRAP EACH FABRIC TOGETHER AT A SUPPORT POST WITH BOTH ENDS FASTENED TO THE POST, WITH A 1-FOOT MINIMUM OVERLAP;
- 4.2. OVERLAP SILT FENCE BY INSTALLING 3-FT. PAST THE SUPPORT POST TO WHICH THE NEW SILT FENCE ROLL IS ATTACHED. ATTACH OLD ROLL TO NEW ROLL WITH HEAVY-DUTY PLASTIC TIES; OR,
- 4.3. OVERLAP ENTIRE WIDTH OF EACH SILT FENCE ROLL FROM ONE SUPPORT POST TO THE NEXT SUPPORT POST. 5. ATTACH FILTER FABRIC TO THE STEEL POSTS USING
- HEAVY-DUTY PLASTIC TIES THAT ARE EVENLY SPACED WITHIN THE TOP 8-INCHES OF THE FABRIC. 6. INSTALL THE SILT FENCE PERPENDICULAR TO THE DIRECTION OF THE STORMWATER FLOW AND PLACE THE

SLOPES TO PROVIDE SEDIMENT STORAGE AND ACCESS FOR

MAINTENANCE AND CLEANOUT. 7. INSTALL SILT FENCE CHECKS (TIE-BACKS) EVERY 50-FT. TO 100-FT., DEPENDENT ON SLOPE, ALONG SILT FENCE THAT IS INSTALLED WITH SLOPE AND WHERE CONCENTRATED FLOWS ARE EXPECTED OR ARE DOCUMENTED ALONG THE PROPOSED/INSTALLED SILT FENCE.

- **POST REQUIREMENTS** 1. SILT FENCE POSTS MUST BE 5-FT. LONG STEEL POSTS THAT MEET, AT A MINIMUM, THE FOLLOWING PHYSICAL CHARACTERISTICS 1.1. COMPOSED OF A HIGH STRENGTH STEEL WITH A
 - MINIMUM YIELD STRENGTH OF 50,000 PSI. 1.2. INCLUDE A STANDARD "T" SECTION WITH A NOMINAL FACE WIDTH OF 1.38-IN. AND A NOMINAL "I" LENGTH
 - OF 1.48-IN. 1.3. WEIGH 1.25 POUNDS PER FOOT (± 8%) 2. POSTS SHALL BE EQUIPPED WITH PROJECTIONS TO AID IN
 - FASTENING OF FILTER FABRIC 3. EACH POST TO BE EQUIPPED WITH SAFETY CAP.
 - 4. STEEL POSTS MAY NEED TO HAVE A METAL SOIL STABILIZATION PLATE WELDED NEAR THE BOTTOM WHEN INSTALLED ALONG STEEP SLOPES OR INSTALLED IN LOOSE SOILS. THE PLATE SHOULD HAVE A MINIMUM CROSS SECTION OF 17-SQUARE INCHES AND BE COMPOSED OF 15 2. USE ONLY FABRIC APPEARING ON SC DOT'S QUALIFIED
 - GAUGE STEEL, AT A MINIMUM. THE METAL SOIL STABILIZATION PLATE SHOULD BE COMPLETELY BURIED. 5. INSTALL POSTS TO A MINIMUM DEPTH OF 24-IN. A MINIMUM HEIGHT OF 1-IN. TO 2-IN. ABOVE THE FABRIC SHALL BE MAINTAINED, AND A MAXIMUM HEIGHT OF 3-FT. 3. 12-IN. OF THE FABRIC SHOULD BE PLACED WITHIN SHALL BE MAINTAINED ABOVE THE GROUND.
- 6. POST SPACING SHALL BE AT A MAXIMUM OF 8-FT. ON CENTER. SILT FENCE THE PROPER DISTANCE FROM THE TOE OF STEEP 7. WOODEN POSTS ARE ALLOWED WHEN CROSSING UTILITIES. ROLLS AND CUT TO THE LENGTH OF THE BARRIER TO OWNER'S DESIGNATED ENVIRONMENTAL REPRESENTATIVE SHALL APPROVE LOCATIONS WHERE WOODEN POST ARE

TO BE USED PRIOR TO INSTALLATION.

FILTER FABRIC -COMPACTED BACKFILL -6-lN, - BURY FILTER FABRIC 6-IN. ----- BURY FILTER FABRIC -& WIRE MESH **SECTION VIEW**

5-FT. STEEL POST -

HEAVY DUTY -

PLASTIC TIES

14 GAUGE WIRE MESH -

- **FABRIC REQUIREMENTS** 1. SILT FENCE MUST BE COMPOSED OF WOVEN GEOTEXTILE FILTER FABRIC THAT CONSISTS OF THE FOLLOWING
- REQUIREMENTS: 1.1. COMPOSED OF FIBERS CONSISTING OF LONG CHAIN SYNTHETIC POLYMERS OF AT LEAST 85% BY WEIGHT OF POLYOLEFINS, POLYESTERS, OR POLYAMIDES THAT ARE FORMED INTO A NETWORK SUCH THAT THE FILAMENTS OR YARNS RETAIN DIMENSIONAL STABILITY RELATIVE
- TO EACH OTHER; 1.2. FREE OF ANY TREATMENT OR COATING WHICH MIGHT ADVERSELY ALTER ITS PHYSICAL PROPERTIES AFTER
- 1.3. FREE OF ANY DEFECTS OR FLAWS THAT SIGNIFICANTLY AFFECT ITS PHYSICAL AND/OR FILTERING PROPERTIES; 1.4. HAVE A MINIMUM WIDTH OF 36-IN.
- PRODUCTS LISTING (QPL), APPROVAL SHEET #34, MEETING THE REQUIREMENTS OF THE MOST CURRENT EDITION OF THE SC DOT STANDARD SPECIFICATIONS FOR HIGHWAY CONSTRUCTION.
- EXCAVATED TRENCH AND SECURED WHEN THE TRENCH IS BACKFILLED
- 4. FILTER FABRIC SHALL BE PURCHASED IN CONTINUOUS AVOID JOINTS.
- 5. FILTER FABRIC SHALL BE INSTALLED AT A MINIMUM OF 24-INCHES ABOVE THE GROUND.

- 6. USE 14 GAUGE WIRE MESH WITH A MAXIMUM OPENING SPACING OF 6-IN. X 6-IN.

INSPECTION & MAINTENANCE


- 1. THE KEY TO FUNCTIONAL SILT FENCE IS WEEKLY INSPECTIONS, ROUTINE MAINTENANCE, AND REGULAR SEDIMENT REMOVAL. 2. ALL SEDIMENT AND EROSION CONTROLS SHALL BE INSPECTED AT LEAST ONCE EVERY SEVEN CALENDAR DAYS AND AFTER ANY STORM EVENT OF GREATER THAN 0.5 INCHES OF PRECIPITATION DURING ANY 24-HOUR PERIOD.
- INSPECTIONS MUST BE CONDUCTED UNTIL FINAL STABILIZATION IS REACHED ON ALL AREAS OF THE CONSTRUCTION SITE. 3. ATTENTION TO SEDIMENT ACCUMULATIONS ALONG THE SILT FENCE IS EXTREMELY IMPORTANT. ACCUMULATED SEDIMENT
- SHOULD BE CONTINUALLY MONITORED AND REMOVED WHEN NECESSARY 4. REMOVE ACCUMULATED SEDIMENT WHEN IT REACHES 1/3 THE HEIGHT OF THE SILT FENCE. 5. REMOVED SEDIMENT SHALL BE PLACED IN STOCKPILE

STORAGE AREAS OR SPREAD THINLY ACROSS DISTURBED


- AREA. STABILIZE THE REMOVED SEDIMENT AFTER IT IS RELOCATED. 6. CHECK FOR AREAS WHERE STORMWATER RUNOFF HAS ERODED A CHANNEL BENEATH THE SILT FENCE, OR WHERE THE FENCE HAS SAGGED OR COLLAPSED DUE TO RUNOFF
- OVERTOPPING THE SILT FENCE. INSTALL CHECKS/TIE-BACKS AND/OR REINSTALL SILT FENCE, AS NECESSARY. 7. CHECK FOR TEARS WITHIN THE SILT FENCE, AREAS WHERE SILT FENCE HAS BEGUN TO DECOMPOSE, AND FOR ANY OTHER CIRCUMSTANCE THAT MAY RENDER THE SILT FENCE INEFFECTIVE. REMOVE DAMAGED SILT FENCE AND REINSTALL
- 8. SILT FENCE SHOULD BE REMOVED WITHIN 30 DAYS AFTER FINAL STABILIZATION IS ACHIEVED AND ONCE IT IS REMOVED, THE RESULTING DISTURBED AREA SHALL BE PERMANENTLY STABILIZED.

NEW SILT FENCE IMMEDIATELY.

DETAIL BASED ON SCDHEC STORM WATER MANAGEMENT BMP HANDBOOK DATED JULY 31, 2005, REVISED MARCH 2014 AND NCDEQ EROSION AND SEDIMENT CONTROL PLANNING AND DESIGN MANUAL, CHAPTERS 6 AND 8 REVISED, MAY 2013.



SINGLE SOCK / SILT FENCE OVERLAP - PLAN VIEW



SINGLE SOCK / SILT FENCE **OVERLAP - SECTION VIEW**

- **GENERAL NOTES** 1. USE FILTREXX® SILTSOXX™ ORIGINAL OR ENGINEER APPROVED EQUIVALENT. REFER TO PLAN
- VIEWS FOR COMPOST FILTER SOCK DIAMETER. 2. TO PREVENT WATER & SEDIMENT FROM FLOWING AROUND THE MEASURES THE TOP COMPOST FILTER SOCK MUST BE PLACED ON THE LIMITS OF DISTURBANCE SIDE OF THE SILT FENCE AT THE
- 3. BACKFILL LOOSE COMPOST OR FINE WOOD CHIPS TO 1/2 THE HEIGHT OF THE COMPOST FILTER SOCK ALONG THE UPSLOPE SIDE, FILLING THE SEAM BETWEEN THE SOIL SURFACE AND THE COMPOST FILTER SOCK.
- 4. T-POST MAY BE USED TO SUBSTITUTE STAKES AS DIRECTED BY THE OWNER'S DESIGNATED
- ENVIRONMENTAL REPRESENTATIVE AS NEEDED BASED UPON FIELD CONDITIONS. 5. FOLLOW MANUFACTURERS SPECIFICATIONS IF THERE IS A DISCREPANCY IN NOTES OR IF

MAINTENANCE NOTES

- 1. ALL SEDIMENT AND EROSION CONTROLS SHALL BE INSPECTED AT LEAST ONCE EVERY SEVEN CALENDAR DAYS AND AFTER ANY STORM EVENT OF GREATER THAN 0.5 INCHES OF PRECIPITATION DURING ANY 24-HOUR PERIOD. INSPECTIONS MUST BE CONDUCTED UNTIL FINAL STABILIZATION IS REACHED ON ALL AREAS OF THE CONSTRUCTION SITE.
- MAKE ANY NECESSARY REPAIRS IMMEDIATELY.

ENGINEER APPROVED ALTERNATIVE IS USED.

- 3. THE MAXIMUM ALLOWABLE ACCUMULATED SEDIMENT IS 1/3 THE HEIGHT OF THE COMPOST FILTER SOCK. HOWEVER, ACCUMULATED SEDIMENT SHOULD BE REMOVED MORE FREQUENTLY. ALTERNATIVELY, A NEW COMPOST FILTER SOCK CAN BE PLACED ON TOP OF AND SLIGHTLY BEHIND THE ORIGINAL ONE CREATING MORE SEDIMENT STORAGE CAPACITY WITHOUT SOIL
- 4. REMOVE ACCUMULATED SEDIMENT TO PROVIDE ADEQUATE STORAGE VOLUME FOR THE NEXT RAIN. TAKE CARE TO AVOID UNDERMINING THE COMPOST FILTER SOCK DURING CLEANOUT. 5. THE COMPOST SOCK MUST BE REPLACED IF CLOGGED OR TORN.
- 6. IF PONDING BECOMES EXCESSIVE, THE COMPOST FILTER SOCK MAY NEED TO BE REPLACED WITH ONE OF A LARGER DIAMETER OR A DIFFERENT MEASURE.
- 7. THE COMPOST FILTER SOCK NEEDS TO BE REINSTALLED IF UNDERMINED OR DISLODGED.
- 8. THE COMPOST FILTER SOCK SHALL BE MAINTAINED UNTIL DISTURBED AREA ABOVE THE DEVICE HAS BEEN PERMANENTLY STABILIZED AND CONSTRUCTION ACTIVITY HAS CEASED.

2016 AYRSLEY TOWN BLVD.

SUITE 2-A

CHARLOTTE, NC 28273

(704) 523-4726

ENGINEERING FIRM

LICENSE NUMBER: F-0176

S&ME, INC.


NO. C00473

PROJECT NUMBER 22350640 DRAWING NUMBER



∕14 \ PERIMETER CONTROL OVERLAP

ISOMETRIC VIEW



GENERAL NOTES

- 1. PREPARE SOIL BEFORE INSTALLING ROLLED EROSION CONTROL PRODUCTS (RECPS), INCLUDING ANY NECESSARY APPLICATION OF LIME, FERTILIZER, AND SEED.
- 2. BEGIN AT THE TOP OF THE SLOPE BY ANCHORING THE RECPS IN A 6-IN. DEEP X 6-IN. WIDE TRENCH WITH APPROXIMATELY 12-IN. OF RECPS EXTENDED BEYOND THE UP-SLOPE PORTION OF THE TRENCH. ANCHOR THE RECPS WITH A ROW OF STAPLES/STAKES APPROXIMATELY 12-IN. APART IN THE BOTTOM OF THE TRENCH. BACKFILL AND COMPACT THE TRENCH AFTER STAPLING. APPLY SEED TO THE COMPACTED SOIL AND FOLD THE REMAINING 12-IN. PORTION OF RECPS BACK OVER THE SEED AND COMPACTED SOIL. SECURE RECPS OVER COMPACTED SOIL WITH A ROW OF STAPLES/STAKES SPACED APPROXIMATELY 12-IN. APART ACROSS THE WIDTH OF THE RECPS.
- 3. ROLL THE RECPS DOWN OR HORIZONTALLY ACROSS THE SLOPE BASED ON ENVIRONMENT INSPECTOR. RECPS WILL UNROLL WITH APPROPRIATE SIDE AGAINST THE SOIL SURFACE. ALL RECPS MUST BE SECURELY FASTENED TO SOIL SURFACE BY PLACING STAPLES/STAKES IN APPROPRIATE LOCATIONS AS SHOWN IN THE STAPLE PATTERN GUIDE.
- 4. THE EDGES OF PARALLEL RECPS MUST BE STAPLED WITH APPROXIMATELY 2
- TO 5-IN. OVERLAP DEPENDING ON THE RECPS TYPE. 5. CONSECUTIVE RECPS SPLICED DOWN THE SLOPE MUST BE END OVER END (SHINGLE STYLE) WITH AN APPROXIMATE 3-IN. OVERLAP. STAPLE THROUGH OVERLAPPED AREA, APPROXIMATELY 12-IN. APART ACROSS ENTIRE RECPS
- 6. IN LOOSE SOIL CONDITIONS, THE USE OF STAPLE OR STAKE LENGTHS GREATER THAN 6-IN. MAY BE NECESSARY TO PROPERLY SECURE THE RECP'S. 7. EROSION CONTROL BLANKET SHALL BE NORTH AMERICAN GREEN BIONET
- SC150BN OR ENGINEER APPROVED EQUIVALENT. 8. FOLLOW MANUFACTURERS SPECIFICATIONS IF THERE IS A DISCREPANCY IN NOTES OR IF ENGINEER APPROVED ALTERNATIVE IS USED.

MAINTENANCE NOTES

- 1. ALL SEDIMENT AND EROSION CONTROLS SHALL BE INSPECTED AT LEAST ONCE EVERY SEVEN CALENDAR DAYS AND AFTER ANY STORM EVENT OF GREATER THAN 0.5 INCHES OF PRECIPITATION DURING ANY 24-HOUR PERIOD. INSPECTIONS MUST BE CONDUCTED UNTIL FINAL STABILIZATION IS REACHED ON ALL AREAS OF THE CONSTRUCTION SITE.
- MAKE ANY NECESSARY REPAIRS IMMEDIATELY. 3. GOOD CONTACT WITH THE GROUND MUST BE MAINTAINED, AND EROSION
- MUST NOT OCCUR BENEATH THE RECP.
- ANY AREAS OF THE RECP THAT ARE DAMAGED OR NOT IN CLOSE CONTACT WITH THE GROUND SHALL BE REPAIRED AND STAPLED.
- IF EROSION OCCURS DUE TO POORLY CONTROLLED DRAINAGE, THE PROBLEM SHALL BE FIXED AND THE ERODED AREA PROTECTED.
- 6. MONITOR AND REPAIR THE RECP AS NECESSARY UNTIL GROUND COVER IS ESTABLISHED.

REFERENCE: DETAIL BASED ON SCDHEC STORM WATER MANAGEMENT BMP HANDBOOK DATED JULY 31, 2015 (PORTIONS REVISED MAY 2014), NORTH AMERICAN GREEN INSTALLATION GUIDE, AND AMERICAN EXCELSIOR CURLEX SLOPE DETAIL ISOMETRIC VIEW.

GENERAL NOTES

CHANNEL BANKS

8 OZ/SY NON-WOVEN

GEOTEXTILE FABRIC

- 1. ROCK CHECK DAMS SHOULD NOT BE PLACED IN WATERS OF THE STATE OR USGS BLUE-LINE STREAMS (UNLESS APPROVED BY FEDERAL AUTHORITIES).
- ROCK CHECK DAMS SHOULD BE INSTALLED IN STEEPLY SLOPED CHANNELS WHERE ADEQUATE VEGETATION CANNOT BE — PLACE STONE OVER ESTABLISHED. THIS BMP MEASURE SHOULD ONLY BE USED IN SMALL

2016 ARSLEY TOWN BLVD

SUITE 2-A

CHARLOTTE, NC 28273

(704) 523-4726

ENGINEERING FIRM

LICENSE NUMBER: F-0176

S&ME, INC.

NO. C00473

PROJECT NUMBER

22350640 DRAWING NUMBER


- OPEN CHANNELS. A 8 OZ/SY NON-WOVEN GEOTEXTILE FABRIC SHALL BE INSTALLED OVER THE SOIL SURFACE WHERE THE ROCK CHECK DAMS IS TO BE
- PLACED. 4. THE BODY OF THE ROCK CHECK DAM SHALL BE COMPOSED OF 12-INCH D50 RIPRAP. THE UPSTREAM FACE MAY BE COMPOSED OF
- 1-INCH D50 WASHED STONE. ROCK CHECK DAMS SHOULD NOT EXCEED A HEIGHT OF 2-FEET AT
- THE CENTERLINE OF THE CHANNEL. 6. ROCK CHECK DAMS SHOULD HAVE A MINIMUM TOP FLOW LENGTH
- OF 2-FEET.
- 7. RIPRAP SHOULD BE PLACED OVER CHANNEL BANKS TO PREVENT WATER FROM CUTTING AROUND THE ROCK CHECK DAM.
- 8. THE RIPRAP SHOULD BE PLACED BY HAND OR MECHANICAL PLACEMENT (NO DUMPING OF ROCK TO FORM DAM) TO ACHIEVE COMPLETE COVERAGE OF THE CHANNEL. DOING SO WILL ALSO ENSURE THAT THE CENTER OF THE CHECK IS LOWER THAN THE
- 9. THE MAXIMUM SPACING BETWEEN THE DAMS SHOULD BE SUCH THAT THE TOE OF THE UPSTREAM CHECK IS AT THE SAME ELEVATION AS THE TOP OF THE DOWNSTREAM CHECK.
- 2. ALL SEDIMENT AND EROSION CONTROLS SHALL BE INSPECTED AT LEAST ONCE EVERY SEVEN CALENDAR DAYS AND AFTER ANY STORM EVENT OF GREATER THAN 0.5 INCHES OF PRECIPITATION DURING ANY 24-HOUR PERIOD. INSPECTIONS MUST
- BE CONDUCTED UNTIL FINAL STABILIZATION IS REACHED ON ALL AREAS OF THE CONSTRUCTION SITE.
- ACCUMULATED SEDIMENT SHOULD BE CONTINUALLY MONITORED AND REMOVED WHEN NECESSARY.
- 5. REMOVED SEDIMENT SHALL BE PLACED IN STOCKPILE STORAGE AREAS OR SPREAD THINLY ACROSS DISTURBED AREA.
- STABILIZE THE REMOVED SEDIMENT AFTER IT IS RELOCATED. 6. INSPECT ROCK CHECK DAMS' EDGES FOR EROSION AND EVIDENCE OF RUNOFF BYPASSING THE INSTALLED CHECK. IF
- EVIDENT REPAIR PROMPTLY AS NECESSARY TO PREVENT EROSION AND BYPASSING.
- 7. IN THE CASE OF GRASS-LINED DITCHES, CHANNELS, AND SWALES, ROCK CHECK DAMS SHOULD BE REMOVED WHEN THE GRASS HAS MATURED SUFFICIENTLY TO PROTECT THE DITCH OR SWALE UNLESS THE SLOPE OF THE SWALE IS GREATER
- SHOULD BE REMOVED IF VEGETATION WILL BE USED FOR PERMANENT EROSION CONTROL MEASURES. THE AREA BENEATH

REFERENCE: DETAIL BASED ON SCDHEC STORM WATER MANAGEMENT BMP HANDBOOK DATED JULY 31, 2005, REVISED MARCH 2014.




GENERAL NOTES

- 1. A FLEXIBLE GROWTH MATRIX (FGM) COMBINES BOTH CHEMICAL AND MECHANICAL BONDING TECHNIQUES TO LOCK THE MATRIX IN PLACE. FGM IS COMPOSED OF CRIMPED, MANMADE FIBERS, ORGANIC FIBERS, AND PERFORMANCE ENHANCING ADDITIVES THAT FORM A LOFTY, INTERLOCKING MATRIX. FGM HAS AIR SPACES AND WATER-ABSORBING CAVITIES THAT IMPROVE SEED GERMINATION, REDUCE THE IMPACT OF RAINDROP ENERGY, AND MINIMIZE SOIL LOSS. WATER INSOLUBLE TACKIFIERS AND FLOCCULANTS
- CHEMICALLY BOND THE MATRIX TO THE SOIL SURFACE. FGM IS APPLICABLE FOR THE FOLLOWING SITUATIONS:
- AS A TYPE A TEMPORARY EROSION CONTROL BLANKET;
- SLOPES UP TO 2H:1V;
- AS AN INFILL FOR TURF REINFORCEMENT MATS (TRMS) ON SLOPES GREATER THAN 2H:1V;
- ENVIRONMENTALLY SENSITIVE AREAS NOT COMPATIBLE FOR NETTING;
- WHEN THE REQUIRED LONGEVITY OF SOIL PROTECTION IS UP TO 1 YEAR; WHEN THE SITE REQUIRES IMMEDIATE EROSION PROTECTION AND THERE IS A RISK OF
- IMPENDING WEATHER;
- WHEN FAST VEGETATION ESTABLISHMENT IS REQUIRED; AND WHEN A HIGH FACTOR OF DESIGN SAFETY IS REQUIRED.
- FGM IS NOT APPLICABLE AS A CHANNEL LINER OR FOR AREAS RECEIVING CONCENTRATED FLOW. APPLICABLE FGM MAY BE SELECTED FROM THE SCDOT APPROVED PRODUCTS LIST.
- FLEXIBLE GROWTH MEDIA (FGM) COMPONENTS ARE PRE-PACKAGED BY THE MANUFACTURER TO ASSURE MATERIAL PERFORMANCE. UNDER NO CIRCUMSTANCES IS FIELD MIXING OF MATERIALS, ADDITIVES OR COMPONENTS ACCEPTED. EXAMINE SUBSTRATES AND CONDITIONS WHERE MATERIALS WILL BE APPLIED.
- APPLY FGM TO GEOTECHNICALLY STABLE SLOPES THAT HAVE BEEN DESIGNED AND CONSTRUCTED TO DIVERT RUNOFF AWAY FROM THE FACE OF THE SLOPE. DO NOT
- PROCEED WITH INSTALLATION UNTIL SATISFACTORY CONDITIONS ARE ESTABLISHED. INSTALL FGM WITH A CONTRACTOR WHO IS CERTIFIED AND TRAINED BY THE
- MANUFACTURER IN THE PROPER PROCEDURES FOR MIXING AND APPLYING THE FGM. STRICTLY COMPLY WITH THE MANUFACTURER'S MIXING RECOMMENDATIONS AND
- INSTALLATION INSTRUCTIONS. USE APPROVED HYDRAULIC SEEDING/MULCHING MACHINES WITH FAN-TYPE NOZZLE (50-
- DEGREE TIP) FOR FGM APPLICATIONS. APPLY FGM FROM OPPOSING DIRECTIONS TO THE SOIL SURFACE IN SUCCESSIVE LAYERS,
- REDUCING THE "SHADOW EFFECT" TO ACHIEVE MAXIMUM COVERAGE OF ALL EXPOSED
- 10. FGM DOES NOT REQUIRE A CURE TIME AND IS EFFECTIVE IMMEDIATELY SUCH THAT FGM MAY BE APPLIED IMMEDIATELY BEFORE, DURING OR AFTER A RAINFALL EVENT.
- 11. INSTALL FGM MATERIALS ACCORDING TO THE MANUFACTURER'S APPLICATION RATES.



18 SEEPAGE DIAPHRAGM DRAIN

7 SCALE: N.T.S



- CALENDAR DAYS AND AFTER ANY STORM EVENT OF GREATER THAN 0.5 INCHES OF PRECIPITATION DURING ANY 24-HOUR PERIOD. INSPECTIONS MUST BE CONDUCTED UNTIL
- FINAL STABILIZATION IS REACHED ON ALL AREAS OF THE CONSTRUCTION SITE. REAPPLY FGM TO DISTURBED AREAS THAT REQUIRE CONTINUED EROSION CONTROL. MAINTAIN EQUIPMENT TO PROVIDE UNIFORM APPLICATION RATES. RINSE ALL MIXING AND
- AND DISCHARGE RINSE WATER APPROPRIATELY. DEGRADATION OF FGM IS EXPECTED TO OCCUR AS A RESULT OF MECHANICAL DEGRADATION, CHEMICAL AND BIOLOGICAL HYDROLYSIS, SUNLIGHT, SALT AND TEMPERATURE. REAPPLY FGM IN ACCORDANCE WITH THE MANUFACTURER'S INSTRUCTIONS. REAPPLICATION IS NOT REQUIRED UNLESS FGM TREATED SOILS ARE DISTURBED OR TURBIDITY OR WATER QUALITY SHOWS THE

NEED FOR AN ADDITIONAL APPLICATION.

APPLICATION EQUIPMENT THOROUGHLY WITH WATER TO AVOID FORMATION OF RESIDUES



CROSS SECTION A-A THRU ROCK CHECK DAM

OVERFLOW

WEIR

∕ 16 \ ROCK CHECK DAM

CHANNEL BOTTOM

12-INCH D50 RIPRAP -

- SCDOT CLASS B RIPRAP

2-FT. MAX.

AT CENTER

2-FT. MAX.

AT CENTER

0.5-FT.

-LENGTH AS REQUIRED IN FIELD

TO KEY INTO SIDE OF SLOPES

NON-WOVEN
GEOTEXTILE FABRIC

L = THE DISTANCE SUCH THAT POINTS A & B ARE OF EQUAL ELEVATION

NON-WOVEN GEOTEXTILE FABRIC

SPACING BETWEEN ROCK CHECK DAMS

A-

TOP OF BANK-

AASHTO #57 WASHED STONE-

AREA WHERE-

SEDIMENT

IS TRAPPED

2-FT. MIN.

TYPICAL ROCK CHECK DAM SECTION

MAINTENANCE NOTES

- 1. THE KEY TO FUNCTIONAL ROCK CHECK DAMS IS WEEKLY INSPECTIONS, ROUTINE MAINTENANCE, AND REGULAR SEDIMENT
- 3. ATTENTION TO SEDIMENT ACCUMULATIONS IN FRONT OF THE ROCK CHECK DAM IS EXTREMELY IMPORTANT.
- 4. REMOVE ACCUMULATED SEDIMENT WHEN IT REACHES 1/3 THE HEIGHT OF THE ROCK CHECK DAM.

- 8. AFTER CONSTRUCTION IS COMPLETED AND FINAL STABILIZATION IS REACHED, THE ENTIRETY OF THE ROCK CHECK DAM THE REMOVED ROCK CHECK DAMS MUST BE ADDRESSED WITH PERMANENT STABILIZATION MEASURES.

